



- OUTLINE SCHEDULE**
- FEB 2015 - REMOVE VEGETATION, PLANT BOUNDARY HEDGEROWS
 - MAY 2015 - REMOVE STUMPS, SPRAY ALLOTMENT SITE TO REMOVE WEEDS, REMOVE TURF
 - INSTALL SUB-BASE TO ACCESS ROAD
 - SOIL PREPARATION (STONE PICK, RIP SUBSOIL TO IMPROVE DRAINAGE, DIG IN MANURE/SPENT WUSHROOM COMPOST)
 - JUNE-AUGUST 2015 - CONSTRUCT ALLOTMENTS (INSTALL WATER SUPPLY, PATHS AND TIMBER EDGES, FINAL SOIL PREPARATION, TOOLBOXES)
 - AUGUST - SEPTEMBER 2015 - TRANSFER FROM EXISTING ALLOTMENTS (TO BE COMPLETED BY 30TH SEPT)

- KEY**
- CRUSHED STONE PATH/ROAD EDGED WITH PCC PIN KERB (60X150MM)
 - CONCRETE GRASSCREEP BACK FILLED WITH GRAVEL, EDGED WITH PCC KERB (145 X100MM)
 - 1.8 X 0.6 x 0.6 M MONO PITCH SOFT WOOD TOOL CHESTS WITH HASP AND PADLOCK TO BE INSTALLED WITH THREE 600X600MM PCC SLABS ON A FLEXIBLE 150MM BEDDING PLANE. ALLOTMENT PLOT NUMBERS TO BE ATTACHED.
 - WATERPOINTS, TO BE WATER TROUGH, WATER CONNECTION AND SUPPLY TO BE CONFIRMED.
 - EXISTING HEDGE BANK AND TREES TO BE RETAINED.
 - 600 WIDE CRUSHED STONE PATH, EDGED WITH TANALIZED SOFT WOOD BOARDS AND PEGGED
 - TIMBER PERGOLAS PLANTED WITH NATIVE CLIMBING PLANTS (HONEYSUCKLE & DOG ROSE)
 - PROPOSED DEVON BANK WITH NATIVE HEDGE, REFER TO PLAN 13750 L94.01 FOR FULL DETAILS.
 - COXES ORANGE PIPIN STANDARDS, ROOT BALLED, 16-18 GIRTH PLANTED WITH 2 SHORT STAKES, UNDER PLANTED WITH FRAGARIA VESCA 2LT POTS AT 8 PER M²
 - DROP OFF AREA
 - 1.5 M HIGH 3 BAR TANALIZED TIMBER FENCE WITH 600MM RABBIT MESH FITTED AT BASE
 - RABBIT PROOF FENCE
 - PROPOSED NOTICE BOARD, TO BE POWDER COATED STEEL FRAME AT A1 SIZE (TO ACCOMMODATE MIN 4X4A)

42 HALF ALLOTMENTS
55 FULL ALLOTMENTS
TOTAL NUMBER 97 PLOTS

NOTES:

FULL EXTENT OF ALLOTMENT TO HAVE A RABBIT PROOF FENCE SET INSIDE THE EXISTING BOUNDARY

NATIVE HEDGEROW TO BE MADE UP OF A DOUBLE STAGGERED ROW OF FEATHERED WHIPS 400MM APART AT 6NO. PER SOM. MIX TO BE MADE UP FROM LONICERA PERICLYMENUM 10% ACER PSEUDOPLATANUS 10% CORYLUS AVELLANA 30% CRATAEGUS MONOGYNA 40% PRUNUS SPINOSA 10% TO BE PLANTED THROUGH HESSMAN DOUBLE PEGGED WEED SUPPRESSING MAT.

ALL BUILD UPS TO ROADS AND FOUNDATION TO STRUCTURES TO BE SUPPLIED BY CIVIL ENGINEERS



TOOL BOXES TO BE SUPPLIED BY ARCH WOOD GREEN HOUSES OR OTHER APPROVED SUPPLIER

lhc architecture urbanism landscape

14/14 Generalist/Urbanist
14/14 Specialist/Urbanist
14/14 Specialist/Urbanist
14/14 Specialist/Urbanist

REVISION DATE COMMENTS AUTHOR/CHIEF

DATE JULY 2014 SCALE 1:250 @A1

DRAWING NO. 13750.L01.S3

DRAWING STATUS PRELIMINARY

DATE JULY 2014 SCALE 1:250 @A1

DRAWING NO. 13750.L01.S3

DRAWING STATUS PRELIMINARY

DATE JULY 2014 SCALE 1:250 @A1

DRAWING NO. 13750.L01.S3

DRAWING STATUS PRELIMINARY