



OUTLINE SCHEDULE

FEB 2015 - REMOVE VEGETATION, PLANT BOUNDARY HEDGEROWS

MAY 2015 - REMOVE STUMPS, SPRAY ALLOTMENT SITE TO REMOVE WEEDS, REMOVE TURF
 - INSTALL SUB-BASE TO ACCESS ROAD
 - SOIL PREPARATION (STONE PICK, RIP SUBSOIL TO IMPROVE DRAINAGE, DIG IN MANURE/SPENT MUSHROOM COMPOST)

JUNE-AUGUST 2015 - CONSTRUCT ALLOTMENTS (INSTALL WATER SUPPLY, PATHS AND TIMBER EDGES, FINAL SOIL PREPARATION, TOOLBOXES)

AUGUST - SEPTEMBER 2015 - TRANSFER FROM EXISTING ALLOTMENTS (TO BE COMPLETED BY 30TH SEPT)

- KEY**
- CRUSHED STONE PATHROAD EDGED WITH PCC PIN KERB (50X150MM)
 - CONCRETE GRASSCRETE BACK FILLED WITH GRAVEL, EDGED WITH PCC KERB (145 X100MM)
 - 1.8 X 0.6 X 0.6 M MONO PITCH SOFT WOOD TOOL CHESTS WITH HASP AND PADLOCK TO BE INSTALLED WITH THREE 600X600MM PCC SLABS ON A FLEXIBLE 150MM BEDDING PLANE. ALLOTMENT PLOT NUMBERS TO BE ATTACHED.
 - WATERPOINTS. TO BE WATER TROUGH, WATER CONNECTION AND SUPPLY TO BE CONFIRMED.
 - EXISTING HEDGE BANK AND TREES TO BE RETAINED.
 - 600 WIDE CRUSHED STONE PATH. EDGED WITH TANALIZED SOFT WOOD BOARDS AND PEGGED
 - TIMBER PERGOLAS PLANTED WITH NATIVE CLIMBING PLANTS (HONEYSUCKLE & DOG ROSE)
 - PROPOSED DEVON BANK WITH NATIVE HEDGE. REFER TO PLAN 13750 L04.01 FOR FULL DETAILS.
 - COXES ORANGE PIPIN STANDARDS. ROOT BALLED, 16-18 GIRTH PLANTED WITH 2 SHORT STAKES. UNDER PLANTED WITH FRAGARIA VESCA 2LT POTS AT 8 PER M2
 - DROP OFF AREA
 - 1.5 M HIGH 3 BAR TANALIZED TIMBER FENCE WITH 600MM RABBIT MESH FITTED AT BASE
 - RABBIT PROOF FENCE
 - PROPOSED NOTICE BOARD. TO BE POWDER COATED STEEL FRAME AT A1 SIZE (TO ACCOMMODATE MIN 4X4)

42 HALF ALLOTMENTS
 55 FULL ALLOTMENTS
 TOTAL NUMBER 97 PLOTS

NOTES:

FULL EXTENT OF ALLOTMENT TO HAVE A RABBIT PROOF FENCE SET INSIDE THE EXISTING BOUNDARY

NATIVE HEDGEROW TO BE MADE UP OF A DOUBLE STAGGERED ROW OF FEATHERED WHIPS 400MM APART AT 140 PER SQM. MIX TO BE MADE UP FROM LONICERA PERICLYMENUM 10% ACER PSEUDOPLATANUS 10% CORYLUS AVELLANA 30% CRATAEGUS MONOGYUA 40% PRUNUS SPINOSA 10% TO BE PLANTED THROUGH HESSIAN DOUBLE PEGGED WEED SUPPRESSING MAT.

ALL BUILD UPS TO ROADS AND FOUNDATION TO STRUCTURES TO BE SUPPLIED BY CIVIL ENGINEERS



TOOL BOXES TO BE SUPPLIED BY ARCH WOOD GREEN HOUSES OR OTHER APPROVED SUPPLIER

		TITLE: ALLOTMENTS AT OTTERY DRAWN: ALLOTMENT LAYOUT DATE: JULY 2014 SCALE: 1:250 @A1 DRAWING NO.: 13750 L01.03 REV: J AUTHOR / CHECKED: DAHPO DRAWING STATUS: PRELIMINARY	
LHC GROUP www.lhc.net	EDEXTER 01502 44034 PLIMMOUTH 01502 88588 SOUTHAMPTON 0900 71965	PL/PO PL/PO AUTHORITY / CHECKED	PL/PO PL/PO AUTHORITY / CHECKED